

## ADDENDUM NO. 1

City of Mercer Island, Washington  
77<sup>th</sup> Ave SE & Sunset Hwy SE Intersection Improvements  
PROJECT NUMBER 22-32

---

DATE OF ADDENDUM ISSUE: October 10, 2022  
DATE OF BID OPENING: October 13, 2022

### NOTE TO ALL PLANHOLDERS:

This Addendum No. 1, containing the following revisions, additions, deletions, and/or clarifications, is hereby made a part of the Plans and Contract Specifications (Contract Documents) for the above-named project. Bidders shall take this Addendum into consideration when preparing and submitting their bids.

Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 in the space provided on the Bid Summary or by signing in the space provided below and submitting the signed addendum with the bid package. Failure to provide this written acknowledge may result in disqualification of the Bidder's submittal.

### CONTRACT SPECIFICATIONS

#### 1. Clarifications:

- Bid Item 16: Not colored
  - Dowels bars shall be placed in both directions.
  - Per SP-85 division 5-05 Colored Scored Cement Concrete Crosswalk shall be measured and paid per cubic yard. The quantity for a common basis of bidding is 70 cubic yards.
- Bid Item 17: Colored, 860 Cobblestone, poured from mixer truck.
- Bid Item 39: Colored, "Brick Red" with Cadman's product code of 79044, or approved equal poured from the mixer truck.
- Bid Item 40: Not Colored
- Bid Item 41: Not Colored
- Bid Item 42: Not Colored

#### 2. Bid Schedule:

**REMOVE PROPOSAL PAGES A-5 THROUGH A-7 AND REPLACE WITH THE ATTACHED PROPOSAL PAGES A-5 THROUGH A-7.**

#### 3. Special Provisions:

**DELETE PARAGRAPH FOUR IN SECTION 8-14.1.**

**REVISE SECTION 5-05.3(10) TO READ:**

Placement of tie bars and dowel bars shall be in accordance with the WSDOT Standard Plan A-40.10-02 in Appendix A. Dowel Bars shall have a minimum diameter of 1-1/4" and no larger than 1-1/2".

---

**ALL OTHER REQUIREMENTS OF THE CONTRACT DOCUMENTS REMAIN IN EFFECT.**

**Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 in the space provided on the Bid Summary Form or by signing in the space provided below and submitting the signed addendum with the bid package.** Failure to provide this written acknowledge may result in disqualification of the Bidder's submittal.

Sincerely,

Lia Klein, PE  
City of Mercer Island  
Transportation Engineer

City of Mercer Island  
77<sup>th</sup> Ave SE & Sunset Highway SE Intersection Improvements

Addendum No. 1  
October 10, 2022  
Page 1

Receipt acknowledge, and conditions agreed to this \_\_\_\_\_ day of \_\_\_\_\_, 2019

Bidder \_\_\_\_\_  
Signature

BID SCHEDULE

SUNSET HWY & 77 <sup>TH</sup> AVE SE INTERSECTION IMPROVEMENTS						
ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
1	1-04	Minor Changes	1	EST	\$25,000	\$25,000
2	1-05	Construction Surveying	1	LS		
3	1-09	Mobilization	1	LS		
4	1-10	Project Temporary Traffic Control	1	LS		
5	2-01	Clearing and Grubbing	1	LS		
6	2-02	Removal of Structures and Obstructions	1	LS		
7	2-02	Asphalt Removal Incl Haul	1840	SY		
8	2-02	Cement Concrete Sidewalk Removal Incl Haul	220	SY		
9	2-02	Cement Concrete Curb and Gutter Removal Incl Haul	670	LF		
10	2-03	Roadway Excavation Incl. Haul	1	LS		
11	2-09	Shoring or Extra Excavation Cl. B	1	LS		
12	4-04	Crushed Surfacing Top Course	1210	TN		
13	5-04	Planing Bituminous Pavement	600	SY		
14	5-04	HMA Cl. 1/2 In. PG 58H-22	200	TN		
15	5-04	Temporary HMA	120	TN		
16	5-05	Cement Concrete Roadway	260	CY		
17	5-05	Scored Cement Concrete Crosswalk	70	CY		
18	7-04	Storm Sewer Pipe 8 In. Diam.	20	LF		
19	7-04	Storm Sewer Pipe 12 In. Diam.	90	LF		
20	7-04	Connection to New Drainage Structure	7	EA		
21	7-05	Catch Basin Type 1	3	EA		
22	7-05	Catch Basin Type 2 48 In. Diam.	2	EA		
23	7-05	Area Drain	1	EA		
24	7-05	Adjust Catch Basin or Manhole	4	EA		
25	7-05	Adjust & Install New Sewer Manhole Frame and Cover	1	EA		
26	7-08	Ductile Iron Watermain, 12" Diam	110	LF		

SUNSET HWY & 77 <sup>TH</sup> AVE SE INTERSECTION IMPROVEMENTS						
ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
27	7-08	2" Blowoff Assembly	1	EA		
28	7-12	Adjust Water Valve Box	11	EA		
29	7-15	Adjust Water Meter Box	3	EA		
30	8-01	Stormwater Pollution Prevention Plan (SWPPP, SPCC)	1	LS		
31	8-01	Erosion Control / Water Pollution Prevention	1	LS		
32	8-02	Property Restoration	1	FA	\$8,750	\$8,750
33	8-04	Cement Concrete Traffic Curb and Gutter	270	LF		
34	8-04	Cement Concrete Traffic Curb	400	LF		
35	8-04	Cement Concrete Extruded Curb Type 6	140	LF		
36	8-09	Raised Pavement Marker Type 1	300	EA		
37	8-09	Raised Pavement Marker Type 2	100	EA		
38	8-13	Monument Adjustment, Case and Cover	1	EA		
39	8-14	Decorative Stamped Cement Concrete Median	40	SY		
40	8-14	Scored Cement Concrete Sidewalk	240	SY		
41	8-14	Cement Concrete Sidewalk	100	SY		
42	8-14	Cement Concrete Driveway Entrance	50	SY		
43	8-14	Detectable Warning Surface	185	SF		
44	8-20	Modifications to Existing Illumination System, Complete	1	LS		
45	8-20	Install Rectangular Rapid Flashing Beacon (RRFB) System, Complete	1	LS		
46	8-21	Permanent Signing	1	LS		
47	8-21	Remove Pavement Markings	1	LS		
48	8-21	Paint Line, 4 Inch	130	LF		
49	8-21	Paint Line, 6 Inch	1030	LF		
50	8-21	Plastic Stop Line	62	LF		
51	8-21	Plastic Traffic Arrow	2	EA		
52	8-21	Plastic Bicycle Symbol	9	EA		
53	8-21	Green Bicycle Lane Treatment	1200	SF		

SUNSET HWY & 77 <sup>TH</sup> AVE SE INTERSECTION IMPROVEMENTS						
ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
54	8-23	Temporary Pavement Markings	1	LS		
55	8-25	Bollards	10	EA		
56	8-26	Detectable Strip	35	LF		

Total Bid  
Amount..... \$ \_\_\_\_\_

**BID SUMMARY**

Unit prices for all items, all extensions, and the total amount of bid must be shown on all Schedules. Where conflict occurs between the unit price and the total amount named for any item, the unit price shall prevail, and the totals shall be corrected to conform thereto.

The bidder shall bid on all items included in the Bid Form.